

Renovation Checklist

PREPARATION BY THE HOMEOWNER PRIOR TO DELIVERY OF CABINETS:

- Remove old cabinets (this is responsibility of homeowner).
- Make all plumbing, heating and electrical changes.
- Complete replacement, relocation or removal of windows, doors and walls.
- Repair walls and ceilings.
- Remove old floor covering.
- Repair or replace sub floor.
- Remove all furniture and accessories from room or cover for protection.
- Remove appliances from room.

INSTALLATION:

- Delivery of cabinets.
- Installation of cabinets.
- Final measurements for countertops.
- Build countertop on site or install pre manufactured.
- Cut out for sinks, cook tops & wall ovens.
- Homeowner is responsible for supplying correct template there will be an extra charge for call backs.
- General clean up and final adjustment of doors.

COMPLETION OF PROJECT BY HOMEOWNERS:

- Installation of plumbing fixtures by plumbing contractor.
- Installation of light fixtures, appliances and trim by electrical contractor.
- Finish coat of paint by painting contractor.
- Installation of finish floor by flooring contractor.
- Final cleaning of interior and exterior of cabinetry, prior to use.